# BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.150

## APPROVED SCHEDULE - B

**Tender Notification No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012**

**Name of Work: Improvements to Road, Construction of Culverts and Drains in Varadarajanagara Gamgamma templeRoad in Ward No. 11, Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of S.M.VARADARAJAPPA | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 134.08 | Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 66.00 | Rupees Sixty Six Only |
| 2 | 405.00 | Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work | Sqm | 50.00 | Rupees Fifty Only |
| 3 | 405.00 | Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 63.00 | Rupees Sixty Three Only |
| 4 | 88.34 | Providing and laying in position **plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs** using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work | Cum | 4136.00 | Rupees Four Thousand One Hundred Thirty Six Only |
| 5 | 17.28 | Providing and constructing granite / trap / basalt size stone masonry in **foundation cement mortar 1:6**, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work | Cum | 2969.00 | Rupees Two Thousand Nine Hundred Sixty Nine Only |
| 6 | 2.16 | Providing and laying in position plain cement concrete of **mix M15 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 4658.00 | Rupees Four Thousand Six Hundred Fifty Eight Only |

S. M. Varadarajappa

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of S.M.VARADARAJAPPA | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 7 | 23.40 | Providing flush pointing to square rubble, course or uncoursed stone masonry with **cement mortar 1:3,** 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 80.00 | Rupees Eighty Only |
| 8 | 186.12 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | Sqm | 232.00 | Rupees Two Hundred Thirty Two Only |
| 9 | 35.57 | Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5561.00 | Rupees Five Thousand Five Hundred Sixty One Only |
| 10 | 28.45 | Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work | Qntl | 7741.00 | Rupees Seven Thousand Seven Hundred Forty One Only |
| 11 | 32.00 | Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification etc complete as per specifications and directions of engineer in charge of the work | M | 141.00 | Rupees One Hundred Forty One Only |

S.M.Varadarajappa

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of S.M.VARADARAJAPPA | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 12 | 52.30 | Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work | Cum | 5238.00 | Rupees Five Thousand Two Hundred Thirty Eight Only |
| 13 | 300.00 | Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc.,etc complete as per specifications and directions of engineer in charge of the work | Sqm | 91.00 | Rupees Ninety One Only |
| 14 | 134.08 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. etc complete as per specifications and directions of engineer in charge of the work | Cum | 71.00 | Rupees Seventy One Only |

S.M. Varadarajappa

**Signature of the Contractor**

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92